



**GENERAL NOTES:**

- FOR THE PURPOSE OF CONSTRUCTION, THE FOLLOWING DEFINITIONS SHALL APPLY:  
 CONTRACTOR-CONSTRUCTION CONTRACTOR  
 OWNER-SENECA NATION OF INDIANS  
 CONSTRUCTION MANAGER-JASON QUINN  
 ENGINEER-JOEL MERRILL, P.E.
- PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTORS SHALL FAMILIARIZE THEMSELVES WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF THE OWNERS REPRESENTATIVE.
- ALL MATERIALS FURNISHED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS, AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY AND THE SENECA NATION OF INDIANS REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- SOME DRAWINGS PROVIDED HERE ARE NOT TO SCALE AND ARE INTENDED TO SHOW OUTLINE ONLY.
- UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES, AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED IN THE DRAWINGS.
- THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENT, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTORS EXPENSE TO THE SATISFACTION OF THE OWNERS REPRESENTATIVE.
- CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS AND OTHER ITEMS REMOVED FROM THE FACILITY.
- CONTRACTOR SHALL LEAVE THE PREMISES IN CLEAN CONDITION.

**SITE WORK NOTES:**

- THE CONTRACTOR TO CONTACT UTILITY LOCATION SERVICES PRIOR TO THE START OF CONSTRUCTION.
- ALL EXISTING ACTIVE WATER, SEWER, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES, AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY THE CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING AROUND OR NEAR UTILITIES.
- ALL SITE WORK SHALL BE AS INDICATED ON THE DRAWINGS AND PROJECT SPECIFICATIONS.
- IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED LEGALLY.
- CONTRACTOR SHALL MINIMIZE DISTURBANCE TO THE SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.

**SENECA NATION  
HEALTH SYSTEM**  
987 RC HOAG DRIVE  
SALAMANCA, NEW YORK 14779

DATE:	REVISED BY:			

NEWTOWN  
WATER TANK PROJECT

SHEET NO.

**2**

OF

**3**

TOTAL SHEETS